

Generalized Geologic Map for Land-Use Planning: Boyle County, Kentucky

Daniel I. Carey and Bart Davidson
Kentucky Geological Survey
Katie Russell
University of Kentucky

Acknowledgments
Geology adapted from Carey and Hettinger (2000), Hettinger (2000), Patton (2000), Sparks and Nuttal (2000), Zhang (2000a, b), and Crawford (2004a, b). Mapped sinkholes from Paylor and others (2004). Thanks to Paul Howell, U.S. Department of Agriculture, Natural Resources Conservation Service, for pond construction illustration. Thanks to Kim and Kent Anness, Kentucky Division of Geographic Information for base map data.

For Planning Use Only
This map is not intended to be used for selecting individual sites. Its purpose is to inform land-use planners, government officials, and the public in general about geologic bedrock conditions that affect the selection of sites for various purposes. The properties of thick soils may supersede those of the underlying bedrock and should be considered on a site-to-site basis. At any site, it is important to understand the characteristics of both the soils and the underlying rock. For further assistance, contact the Kentucky Geological Survey, 850 257 5500. For more information, and to make custom maps of your area, visit the KGS Land-Use Planning Internet Mapping Web Site at kgmap.uky.edu/websets/kyuplan/viewer.htm.



The Knobs
The Knobs are isolated, steep-sloping, often cone-shaped hills that dominate the horizon of southern Boyle County. They were originally continuous with the Mississippi Plateau, but were separated from the plateau by stream erosion. Many of the knobs are still capped by erosion-resistant limestones or sandstones. The sharp slopes of the Knobs are composed of shales of the 350-million-year-old Mississippian Borden Formation, which are more easily eroded than the overlying limestones and sandstones. The base of the Knobs contains Devonian black shales. Photo by Dan Carey, Kentucky Geological Survey.

Limestone, Dolomite (Unit 4)



The lower 5 feet of unit 4 is a shaly, silty limestone, as seen in the lower section of this roadcut off Ky. 37. Photo by Dan Carey, Kentucky Geological Survey.

Wastewater Treatment



Abandoned limestone quarry off U.S. 68 north of Perrysville has been incorporated into the city's wastewater treatment system. Photo by Dan Carey, Kentucky Geological Survey.

- EXPLANATION**
- School
 - Geologic fault
 - Concealed geologic fault
 - Railroad
 - County line
 - Incorporated city boundary
 - Watershed boundary
 - Public lands
 - Designated flood zone (FEMA, 2004)
 - Wetlands > 1 acre (U.S. Fish and Wildlife Service, 2003)
 - Source-water protection area, zone 1
 - Quarry
 - Mapped sinkholes
 - Artificial fill
 - Water wells:
 - Domestic
 - Monitoring
 - Public
 - Agricultural
 - Severely eroded area
 - Rock outcrop
 - Sinkhole
 - Wet area
 - Mine or quarry
 - Spring
 - 50-foot contour interval
 - Photo location

*Flood information is available from the Kentucky Division of Water, Flood Plain Management Branch, www.water.ky.gov/floods/.

Source-Water Protection Areas
Source-water protection areas are those in which activities are likely to affect the quality of the drinking-water source. For more information, see kgweb.uky.edu/download/water/wapp/wapp.htm.

Alluvium
Alluvium deposited by the North Rolling Fork provides soils for agriculture and sites for peaceful rural living. Photo by Dan Carey, Kentucky Geological Survey.


Radon
Radon gas can be a local problem, in some areas exceeding the U.S. Environmental Protection Agency's maximum recommended limit of 4 picocuries per liter. Radon from soil gas that enters the home from below through cracks and gaps is the main cause of radon problems. The shales of unit 9 and limestones of unit 3 may contain high levels of uranium or radium, parent materials for radon gas. Homes in these areas should be tested for radon. Testing is inexpensive and easy, taking only a few minutes. Radon reduction systems work and are not too costly. Even high levels can be reduced to acceptable levels. The EPA recommends action be taken if indoor levels exceed 4 picocuries per liter, which is 10 times the average outdoor level. (U.S. EPA, 2005)

Radon Risk if You've Never Smoked (U.S. Environmental Protection Agency, 2005)

Radon Level	If 1,000 people who never smoked were exposed to this level over a "lifetime"	The risk of cancer from radon exposure is approximately	WHAT TO DO:
20 pCi/L	About 36 people could get lung cancer	35 times the risk of dying	Fix your home
10 pCi/L	About 18 people could get lung cancer	20 times the risk of dying in a lifetime	Fix your home
8 pCi/L	About 15 people could get lung cancer	4 times the risk of dying in a lifetime	Fix your home
4 pCi/L	About 7 people could get lung cancer	The risk of dying in a car crash	Fix your home
2 pCi/L	About 4 people could get lung cancer	The risk of dying from poison	Consider fixing between 2 and 4
1.3 pCi/L	About 2 people could get lung cancer	(Average indoor radon level)	(Reducing radon levels below 2 pCi/L is difficult)
0.4 pCi/L		(Average outdoor radon level)	

Note: If you are a former smoker, your risk may be higher.
* Lifetime risk of lung cancer deaths from EPA Assessment of Risks from Radon in Homes (EPA 402-R-03-003).
** Comparison data calculated using the Centers for Disease Control and Prevention's 1999-2001 National Center for Injury Prevention and Control Reports.


North Rolling Fork
Limestone of unit 4 forms the bed of the upper North Rolling Fork. Photo by Dan Carey, Kentucky Geological Survey.





Learn more about Kentucky geology at www.uky.edu/KGS/kyokey/



Boyle County, an area of 182 square miles, lies in four physiographic provinces: northern Boyle in the Outer and Inner Bluegrass Region, and southern Boyle in the Mississippian Plateau and Knobs. The highest point in the county, 1,364 feet, is Parkville Knob. The lowest elevation, 740 feet, is where the North Rolling Fork leaves the county. The 2005 population was 27,990, 1 percent more than in 2000. Photo by Bart Davidson, Kentucky Geological Survey.



Radon Ventilation
Ventilation system removes radon from the basement area of this home on unit 9. Photo by Dan Carey, Kentucky Geological Survey.



Mapped Surface Faults
Faults are common geologic structures across Kentucky, and have been mapped in many of the Commonwealth's counties. The faults shown on this map represent seismic activity that occurred several million years ago at the latest. There has been no activity along these faults in recorded history. Seismic risk associated with these faults is very low. Faults may be associated with increased fracturing of bedrock in the immediately adjacent area. This fracturing may influence slope stability and groundwater flow in these limited areas.

References Cited

American Institute of Professional Geologists, 1993. The citizens' guide to geologic hazards: 134 p.

Carey, D.I., and Hettinger, C.P., 2000. Spatial database of the Bryantville quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-945. Adapted from Wilcoit, O.E., and Cressman, E.R., 1971. Geologic map of the Bryantville quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-945, scale 1:24,000.

Carey, D.I., and Stokney, J.F., 2004. Groundwater resources of Boyle County, Kentucky. Kentucky Geological Survey, ser. 12. County Report 11.

www.uky.edu/KGS/water/ibary/gwbas/BoyleBoyle.htm [accessed 8/24/06]

Currens, J.C., 2001. Protecting Kentucky's karst aquifers from nonpoint-source pollution: Kentucky Geological Survey, ser. 12. Map and Chart 27, 1 sheet.

Cradock, W.H., 1983. Soil survey of Boyle and Mercer Counties, Kentucky. U.S. Department of Agriculture, Soil Conservation Service, 148 p.

Crawford, M.M., 2004a. Spatial database of the Gravel Switch quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-1494. Adapted from Moore, S.L., 1978. Geologic map of the Gravel Switch quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1494, scale 1:24,000.

Crawford, M.M., 2004b. Spatial database of the Mackville quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-1378. Adapted from Johnson, W.L., 1977. Geologic map of the Mackville quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1378, scale 1:24,000.

Federal Emergency Management Agency, 2004. www.fema.gov [accessed 8/20/06]

Hettinger, C.P., 2000. Spatial database of the Parkville quadrangle, Boyle and Casey Counties, Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-1157. Adapted from Shawe, F.R., and Wigley, P.B., 1974. Geologic map of the Parkville quadrangle, Boyle and Lincoln Counties, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1157, scale 1:24,000.

Hettinger, C.P., 2000. Spatial database of the Parkville quadrangle, Boyle and Casey Counties, Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-1494. Adapted from Moore, S.L., 1978. Geologic map of the Parkville quadrangle, Boyle and Casey Counties, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1494, scale 1:24,000.

Paylor, R.L., Flores, L., Caudill, M., and Currens, J.C., 2004. A GIS coverage of karst sinkholes in Kentucky. Kentucky Geological Survey, ser. 12. Digital Publication 5, 1 CD-ROM.


Patton, J.A., 2000. Spatial database of the Danville quadrangle, Mercer and Boyle Counties, Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-1165. Adapted from Cressman, E.R., 1974. Geologic map of the Danville quadrangle, Mercer and Boyle Counties, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1165, scale 1:24,000.

U.S. Fish and Wildlife Service, 2003. National Wetlands Inventory, www.nwi.fws.gov [accessed 8/24/06]

U.S. Environmental Protection Agency, 2005. A citizen's guide to radon: The guide to protecting yourself and your family from radon. www.epa.gov/radon/quickguide.html [accessed 8/18/11]

Zhang, Q., 2000a. Spatial database of the Danville quadrangle, Mercer and Boyle Counties, Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-985. Adapted from Cressman, E.R., 1972. Geologic map of the Danville quadrangle, Mercer and Boyle Counties, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-985, scale 1:24,000.


Zhang, Q., 2000b. Spatial database of the Junction City quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12. Digitally Vectorized Geologic Quadrangle Data DVGQ-981. Adapted from Harris, L.D., 1972. Geologic map of the Junction City quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-981, scale 1:24,000.



Perrysville
Seven thousand five hundred men were killed or wounded on October 8, 1862 in the fields north of Perrysville. The Battle of Perrysville was the largest Civil War battle in Kentucky. Photo by Dan Carey, Kentucky Geological Survey.



Herrington Lake
Herrington Lake, seen here from the Coffey Cove Marina, provides fishing and boating recreation, and is the county's primary water source. Nearly everyone in the county has access to public water. Limestones of unit 3 line the banks. Photo by Dan Carey, Kentucky Geological Survey.



Karst Geology
Karst areas in Boyle County are indicated by sinkholes. The term "karst" refers to a landscape characterized by sinkholes, springs, sinking streams (streams that disappear underground), and underground drainage through solution-enlarged conduits or caves. Karst landscapes form when slightly acidic water from rain and snowmelt seeps through soil cover into fractured and soluble bedrock (usually limestone, dolomite, or gypsum). Sinkholes are depressions on the land surface into which water drains underground. Usually circular and often funnel-shaped, they range in size from a few feet to hundreds of feet in diameter. Springs occur when water emerges from underground to become surface water. Caves are solution-enlarged fractures or conduits large enough for a person to enter.




Karst Subsidence
Limestone terrain can be subject to subsidence hazards, which usually can be overcome by prior planning and site evaluation. "A" shows construction above an open cavern, which later collapses. This is one of the most difficult situations to detect, and the possibility of this situation beneath a structure warrants insurance protection for homes built on karst terrain. In "B" a heavy structure presumed to lie above soft bedrock actually is partially supported on soft, residual clay soils that subside gradually, resulting in damage to the structure. This occurs where inadequate site evaluation can be traced to lack of geophysical studies and inadequate core sampling. "C" and "D" show the close relationship between hydrology and subsidence hazards in limestone terrain. In "C" the house is situated on porous fill (light shading) at a site where surface- and groundwater drainage move supporting soil (discretion shading) into voids in limestone (blocks) below. The natural process is then accelerated by infiltration through fill around the house. "D" shows a karst site where normal rainfall is absorbed by subsurface conduits, but water from infrequent heavy storms cannot be carried away quickly enough to prevent flooding of low-lying areas. Adapted from AIFP (1993).

Rural Residential Development



Rural residential development off U.S. 68 north of Perrysville. Limestones of unit 6 provide soils for an agricultural economy and attractive sites for development. Conflicting land-use interests can often be accommodated with thoughtful planning. Photo by Dan Carey, Kentucky Geological Survey.

Environmental Protection



- Never use sinkholes as dumps. All waste, but especially pesticides, paints, household chemicals, automobile batteries, and used motor oil, should be taken to an appropriate recycling center or landfill.
 - Make sure runoff from parking lots, streets, and other urban areas is routed through a detention basin and sediment trap to filter it before it flows into a sinkhole.
 - Keep cattle and other livestock out of sinkholes and sinking streams. There are other methods of providing water to livestock.
 - Make sure your home septic system is working properly and that it's not discharging sewage into a crevice or sinkhole.
 - Keep cattle and other livestock out of sinkholes and sinking streams. There are other methods of providing water to livestock.
 - See to it that sinkholes near or in crop fields are bordered with trees, shrubs, or grass buffer strips. This will filter runoff flowing into sinkholes and also keep filled areas away from sinkholes.
 - Construct waste-holding lagoons in karst areas carefully, to prevent the bottom of the lagoon from collapsing, which would result in a catastrophic emptying of waste into the groundwater.
 - If required, develop a groundwater protection plan (410KAR5-037) or an agricultural water-quality plan (KRS224-71) for your land use.
- (From Currens, 2001)

Groundwater

In the northern half of the county, within the larger creek and river valleys, most drilled wells will produce enough water for a domestic supply at depths of less than 100 feet. In the rest of Boyle County, wells located in the larger creek valleys will produce enough water for a domestic supply, except during dry weather. In upland areas (85 percent of the county) most drilled wells will not produce enough water for a dependable domestic supply; some wells along drainage lines may produce enough water, except during dry weather. Throughout the county, groundwater is hard or very hard and may contain salt or hydrogen sulfide, especially at depths greater than 100 feet. For more information on groundwater in the county, see Carey and Stokney (2004).

Additional Resources for Boyle County

- Listed below are Web sites for several agencies and organizations that may be of assistance with land-use planning issues in Boyle County:
- www.danville-ky.com Boyle County Community Development Council
 - www.annex.com Advocate-Messenger
 - www.uky.edu/boyle/ UK Cooperative Extension Service
 - www.kincinet.net/kyrc/kyr.htm Kentucky Heritage Resource Conservation and Development Council
 - www.thinkkentucky.com/edia/cmty/cw/cw114 Kentucky Economic Development Information System
 - www.thinkkentucky.com/edia/cmty/cw/cw114 Detailed county statistics
 - www.uky.edu/KentuckyAtlas21021.htm Kentucky Atlas and Gazetteer, Boyle County
 - quickfacts.census.gov/qfd/states/21/21021.html U.S. Census data
 - www.kgsweb.uky.edu/ResidentialRadonQandA.htm Radon in the home
 - kgweb.uky.edu/download/misc/landuse/main/kyuplan.htm Planning information from the Kentucky Geological Survey

LAND-USE PLANNING TABLE DEFINITIONS

FOUNDATION AND EXCAVATION

The terms "earth" and "rock" excavation are used in the engineering sense; earth can be excavated by hand tools, whereas rock requires heavy equipment or blasting to remove.

LIMITATIONS

Slight: A slight limitation is one that commonly requires some corrective measure but can be overcome without a great deal of difficulty or expense.

Moderate: A moderate limitation is one that can normally be overcome but the difficulty and expense are great enough that completing the project is questionable.

Severe: A severe limitation is one that is difficult to overcome and commonly is not feasible because of the expense involved.

LAND USES

Septic tank disposal system: A septic tank disposal system consists of a septic tank and a filter field. The filter field is a subsurface tile system laid in such a way that effluent from the septic tank is distributed with reasonable uniformity into the soil.

Residences: Ratings are made for residences with basements because the degree of limitation is dependent upon ease and required depth of excavation. For example, excavation in limestone has greater limitation than excavation in shale for a house with a basement.

Highways and streets: Refers to paved roads in which cuts and fills are made in hilly topography, and considerable work is done preparing subgrades and bases before the surface is applied.

Access roads: These are low-cost roads, driveways, etc., usually surfaced with crushed stone or a thin layer of blacktop. A minimum of cuts and fills are made, little work is done preparing a subgrade, and generally only a thin base is used. The degree of limitation is based on year-around use and would be less severe if not used during the winter and early spring. Some types of recreation areas would not be used during these seasons.

Light industry and malls: Ratings are based on developments having structures or equivalent load limit requirements of three stories or less, and large paved areas for parking lots. Structures with greater load limit requirements would normally need footings in solid rock, and the rock would need to be core drilled to determine the presence of caverns, cracks, etc.


Intensive recreation: Athletic fields, stadiums, etc.

Extensive recreation: Camp sites, picnic areas, parks, etc.

Reservoir areas: The floor of the area where the water is impounded. Ratings are based on year-around use and would be less severe if not used during the winter and early spring.


Reservoir embankments: The rocks are rated on limitations for embankment material.

Underground utilities: Included in this group are sanitary sewers, storm sewers, water mains, and other pipes that require fairly deep trenches.




Swelling and Shrinking Shales
A problem of some concern in Boyle County is the swelling of some of the clay minerals in shale units 8 and 9. The process is exacerbated when the shale contains the mineral pyrite (fool's gold). Pyrite is a common mineral and can be found distributed throughout the black shale, although it is not always present and may be discontinuous both laterally and horizontally. In the presence of moisture and oxygen, pyrite oxidizes and produces sulfuric acid. The acid reacts with calcium carbonates found in water, the rock itself, crushed limestone, and concrete. This chemical reaction produces sulfate and can form the mineral gypsum, whose crystallization can cause layers of shale to expand and burst, backfill to swell, and concrete to crack and crumble. It can heave the foundation, the slab, and interior partitions resting on it, and damage upper floors and interior partitions. This phenomenon has been responsible for extensive damage to schools, homes, and businesses in Boyle County. During times of drought, these same shales may shrink, causing foundations to drop.

Anyone planning construction on these shales should seek professional advice from a geologist or engineer familiar with the problem.



Pond Construction
Anti-Leakage Strategy
Deny water access to permeable materials and/or alter materials to an impermeable condition



Pond Construction
Successful pond construction must prevent water from seeping through structured soils into limestone solution channels below. A compacted clay liner or artificial liner may prevent pond failure. Getting the basin filled with water as soon as possible after construction prevents drying and cracking, and possible leakage, of the clay soil liner. Ponds constructed in dry weather are more apt to leak than ponds constructed in wet weather. A geotechnical engineer or geologist should be consulted regarding the requirements of a specific site. Other leakage prevention measures include synthetic liners, bentonite, and asphaltic emulsions. The U.S. Department of Agriculture, Natural Resources Conservation Service can provide guidance on the application of these liners to new construction, and for treatment of existing leaking ponds.

Dams should be constructed of compacted clayey soils at slopes flatter than three units horizontal to one unit vertical. Ponds with dam heights exceeding 25 feet, or pond volumes exceeding 50 acre-feet, require permits. Contact the Kentucky Division of Water, 14 Reilly Rd., Frankfort, KY 40601, telephone: 502.564.3410. Illustration by Paul Howell, U.S. Department of Agriculture, Natural Resources Conservation Service.

Planning Guidance by Rock Unit Type

Rock Unit	Foundation and Excavation	Septic System	Residence with Basement	Highways and Streets	Access Roads	Light Industry and Malls	Intensive Recreation	Extensive Recreation	Reservoir Areas	Reservoir Embankments	Underground Utilities
1. Silt, sand, and gravel	Fair foundation material; easy for foundation work. Seasonal high water table. Subject to flooding.	Severe limitations. Refer to soil report (CRSd-003).	Water in alluvium. Seasonal high water table. Subject to flooding. Refer to soil report (CRSd-003).	Slight limitations. Refer to soil report (CRSd-003).	Slight limitations. Refer to soil report (CRSd-003).	Moderate to slight limitations. Refer to soil report (CRSd-003).	No limitations.	No limitations.	Previous material. Refer to soil report (CRSd-003).	Fair stability. Fair hazard. Refer to soil report (CRSd-003).	Slight limitations. Refer to soil report (CRSd-003).
2. Silt, sand, and gravel (trace carbonate)	Good foundation material; easy to excavate.	Severe to moderate limitations. Possible groundwater contamination.	Slight limitations.	No limitations.	No limitations.	No limitations.	No limitations.	Moderate to slight limitations. Sleep eroded slopes. Potential for land mine or natural history park.	Not applicable.	Not applicable.	Slight limitations.
3. Limestone	Excellent foundation material; difficult to excavate.	Severe limitations. Impervious rock. Locally fat drainage through fractures and sink to water table, with possible contamination.	Severe to moderate limitations. Rock excavation; locally upper few feet may be repetitive. Seasonal high water table. Refer to soil report (CRSd-003).	Slight to moderate limitations. Rock excavation; locally upper few feet may be repetitive. Seasonal high water table. Refer to soil report (CRSd-003).	Moderate to moderate limitations. Rock excavation; locally narrow ravines. Refer to soil report (CRSd-003).	Slight to moderate limitations. Rock excavation; locally upper few feet may be repetitive. Seasonal high water table. Refer to soil report (CRSd-003).	No limitations.	Moderate to slight limitations. Sleep eroded slopes. Potential for land mine or natural history park.	Severe limitations. Reservoir may leak where rocks are fractured. Sinks possible.	Severe limitations.	Severe limitations. Rock excavation.
4. Limestone, dolomite	Excellent foundation material; difficult to excavate.	Moderate to severe limitations. Impervious rock. Locally fat drainage through fractures and sink to water table, with possible contamination.	Severe limitations. Rock excavation.	Severe limitations. Rock excavation.	Severe to moderate limitations. Rock excavation.	Slight to moderate limitations. Rock excavation; locally narrow ravines. Refer to soil report (CRSd-003).	No limitations.	Slight to moderate limitations. Sleep eroded slopes. Potential for land mine or natural history park.	Moderate to moderate limitations. Reservoir may leak where rocks are fractured. Sinks possible.	Moderate to moderate limitations. Reservoir may leak where rocks are fractured. Sinks possible.	Severe limitations. Rock excavation.
5. Limestone, sandstone, siltstone	Excellent foundation material; difficult to excavate.	Severe limitations. Impervious rock. Locally fat drainage through fractures and sink to water table, with possible contamination.	Moderate to severe limitations. Rock excavation may be required.	Severe limitations. Rock excavation. Possible steep slopes.	Severe to moderate limitations. Rock excavation may be required. Possible steep slopes.	Severe to moderate limitations. Rock excavation may be required. Possible steep slopes.	Severe to moderate limitations. Rock excavation may be required.	Severe to slight limitations. Sleep eroded slopes. Potential for land mine or natural history park.	Slight to moderate limitations. Reservoir may leak where rocks are fractured.	Severe limitations. Reservoir may leak where rocks are fractured.	Severe limitations. Rock excavation.
6. Limestone and shale	Good to excellent foundation material; difficult to excavate.	Severe to moderate limitations. Impervious rock. Locally fat drainage through fractures and sink to water table, with possible contamination.	Severe to moderate limitations. Rock excavation possible.	Moderate to severe limitations. Rock excavation. Possible steep slopes.	Slight to moderate limitations. Rock excavation. Possible steep slopes.	Slight to moderate limitations. Rock excavation. Possible steep slopes.	No limitations.	Slight to moderate limitations. Sleep eroded slopes. Potential for land mine or natural history park.	Slight to moderate limitations. Reservoir may leak where rocks are fractured. Sinks possible.	Moderate to severe limitations. Reservoir may leak where rocks are fractured. Sinks possible.	Moderate to severe limitations. Rock excavation likely.
7. Shale and limestone	Good to excellent foundation material; difficult to excavate.	Severe limitations. Impervious rock.	Slight to moderate limitations. Rock excavation. Possible steep slopes.	Slight to moderate limitations. Rock excavation. Possible steep slopes.	Slight to moderate limitations. Rock excavation. Possible steep slopes.	Slight to moderate limitations. Rock excavation. Possible steep slopes.	No limitations.	No limitations.	Slight limitations. Most favorable sites are in the unit locally, impervious rock and underlain by fractured limestone.	Slight limitations. Reservoir may leak where rocks are fractured.	Moderate to moderate limitations. Rock excavation likely.
8. Siltstone and shale*	Siltstone, fair to good foundation material; difficult to excavate. See unit 9 for shale.	Severe limitations. This soil is low permeability.	Severe limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Severe limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Severe limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Severe limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Severe to moderate limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Severe to moderate limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Moderate to slight limitations. Reservoir may leak where rocks are fractured.	Moderate to slight limitations. Reservoir may leak where rocks are fractured.	Severe limitations. Rock excavation. See unit 9 for shale.
9. Shale*	Fair to poor foundation material; difficult to excavate. Possible expansion of clay in particularly poor foundation.	Severe limitations. Low permeability.	Severe limitations. Low strength, slumping, and swelling of shales. Possible expansion of clay in particularly poor foundation.	Moderate to severe limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Moderate to severe limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Moderate to severe limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Severe to slight limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Moderate to slight limitations. Rock excavation. Possible steep slopes. See unit 9 for shale.	Moderate to slight limitations. Reservoir may leak where rocks are fractured. Sinks possible.	Moderate to slight limitations. Reservoir may leak where rocks are fractured. Sinks possible.	Moderate to moderate limitations. Rock excavation. See unit 9 for shale.

* See discussions of swelling shales and soils and slope stability