

Generalized Geologic Map for Land-Use Planning: Marion County, Kentucky

Daniel I. Carey and Garland R. Dever, Jr.
Kentucky Geological Survey

Adam Pike
University of Kentucky
Acknowledgments

Geology adapted from Crawford (2004a-c), Johnson (2004), Murphy (2004a, b), Nelson (2004a-e), and Petersen (2004a, b). Mapped sinkholes from Taylor and others (2004). Thanks to Paul Howell, U.S. Department of Agriculture, Natural Resources Conservation Service, for pond construction illustration. Thanks to Mike Carey, St. Augustine School, for photo assistance. Thanks to Kim and Kent Anness, Kentucky Division of Geographic Information, for base map data.

For Planning Use Only

This map is not intended to be used for selecting individual sites. Its purpose is to inform land-use planners, government officials, and the public in a general way about geologic bedrock conditions that affect the selection of sites for various purposes. The properties of thick soils may supersede those of the underlying bedrock and should be considered on a site-to-site basis. At any site, it is important to understand the characteristics of both the soils and the underlying rock. For further assistance, contact the Kentucky Geological Survey, 859.257.5500. For more information, and to make custom maps of your area, visit the KGS Land-Use Planning Internet Mapping Web Site at kgsmap.uky.edu/web/site/kyplanviewer.htm.

Marion County Courthouse



Marion County, an area of 346 square miles, was established in 1834. The 2006 population was 16,754 (54 people per square mile), 10.4 percent larger than in 1990. The county includes parts of the Outer Bluegrass, Knobs, and Mississippian Plateau Regions. The southern boundary of the county approximates the position of Mudraugh Hill, a regional escarpment. The highest point in the county is Putnam Knob, 1,260 feet, about 6 miles east of Lebanon. The lowest elevation, 475 feet, is where Hardin Creek leaves the northern tip of the county. The geographic center of Kentucky is in Marion County, just northwest of Lebanon. Photo by Dan Carey, Kentucky Geological Survey.

Mapped Surface Faults

Faults are common geologic structures across Kentucky, and have been mapped in many of the Commonwealth's counties. The faults shown on this map represent seismic activity that occurred several million years ago at the latest. There has been no activity along these faults in recorded history. Seismic risk associated with these faults is very low. Faults may be associated with increased fracturing of bedrock in the immediately adjacent area. This fracturing may influence slope stability and groundwater flow in these limited areas.

Radon Ventilation




Ventilation system removes radon from the basement area of this home on unit 5. Photo by Dan Carey, Kentucky Geological Survey.

Planning Guidance by Rock Unit Type

Rock Unit	Foundation and Excavation	Septic System	Residence with Basement	Highways and Streets	Access Roads	Light Industry and Malls	Intensive Recreation	Extensive Recreation	Reservoir Areas	Reservoir Embankments	Underground Utilities
1. Clay, silt, sand, and gravel (alluvium)	Fair foundation material; easy to excavate.	Severe limitations. Failed septic systems can contaminate groundwater. Refer to soil report (Kelley and Craddock, 1991).	Severe limitations. Water in alluvium may be in direct contact with basements. Refer to soil report (Kelley and Craddock, 1991).	Moderate to severe limitations. Seasonal high water table. Subject to flooding. Refer to soil report (Kelley and Craddock, 1991).	Severe limitations. Seasonal high water table. Subject to flooding. Refer to soil report (Kelley and Craddock, 1991).	Severe limitations. Seasonal high water table. Subject to flooding. Refer to soil report (Kelley and Craddock, 1991).	Subject to flooding. Refer to soil report (Kelley and Craddock, 1991).	Subject to flooding. Refer to soil report (Kelley and Craddock, 1991).	Previous material. Seasonal high water table. Subject to flooding. Refer to soil report (Kelley and Craddock, 1991).	Fair stability. Fair compaction characteristics. Piping hazard and Refer to soil report (Kelley and Craddock, 1991).	Moderate to severe limitations. Wetness. Footing. Refer to soil report (Kelley and Craddock, 1991).
2. Silt, clay, sand, and gravel (terrace deposits)	Fair to good foundation material; easy to excavate.	Moderate to severe limitations, depending on amount of soil cover.	Slight to moderate limitations.	Slight limitations.	Slight limitations.	Slight limitations.	Moderate to slight limitations, depending on activity and slope.	Slight limitations.	Not recommended. Previous material.	Not recommended. Previous material.	Moderate limitations. Possible rock excavation.
3. Limestone, dolomite	Excellent foundation material; difficult to excavate.	Moderate to severe limitations. Impervious shale rock. Locally fast fractures and sinkholes. Locally fast fractures with possible contamination.	Severe limitations. Rock excavation.	Severe limitations. Rock excavation.	Moderate to severe limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Rock excavation. Upper few feet may be repeatable.	Moderate limitations. Reservoir may leak where rocks are fractured. Fractures possible. Local drainage problems.	Moderate limitations. Reservoir may leak where rocks are fractured. Fractures possible.	Severe limitations. Rock excavation.
4. Limestone and shale	Fair to good foundation material; moderately difficult to excavate.	Severe limitations. Impervious rock. Locally fast fractures through fractures to water table, with possible contamination.	Severe limitations. Rock excavation.	Moderate to severe limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Rock excavation. Upper few feet may be repeatable.	Slight to moderate limitations. Reservoir may leak where rocks are fractured.	Severe limitations. Reservoir may leak where rocks are fractured.	Moderate to severe limitations. Possible rock excavation.
5. Shale*	Fair to poor foundation material; easy to modify. Possible expansion of shales. Plastic clay is particularly poor foundation.	Severe limitations. Low permeability.	Severe limitations. Low permeability. Strong slumping, and seepage problems. Strength slumping, and seepage problems.	Moderate to severe limitations. Rock excavation. Steep slopes. Strength slumping, and seepage problems.	Moderate to severe limitations. Rock excavation. Steep slopes. Strength slumping, and seepage problems.	Moderate to severe limitations. Rock excavation. Steep slopes. Strength slumping, and seepage problems.	Severe to slight limitations, depending on activity and topography.	Moderate to slight limitations, depending on activity and topography.	Slight limitations. Reservoir may leak where rocks are fractured. Ponds on shale are successful.	Severe limitations. Poor strength and stability.	Moderate limitations. Poor strength, wetness.
6. Siltstone and shale*	Siltstone. Fair to good foundation material; difficult to excavate. See unit 5 for shale.	Severe limitations. This shale and low permeability. See unit 5 for shale.	Severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe to moderate limitations, depending on activity and topography.	Severe to slight limitations, depending on activity and topography.	Moderate to severe limitations. Reservoir may leak where rocks are fractured.	Moderate to severe limitations. Reservoir may leak where rocks are fractured.	Severe limitations. Rock excavation. Steep slopes.
7. Siltstone, dolomite, and limestone	Excellent foundation material; difficult to excavate.	Severe limitations. This shale and impervious rock. See unit 5 for shale.	Moderate to severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe limitations. Rock excavation. Steep slopes. See unit 5 for shale.	Severe to moderate limitations, depending on activity and topography.	Severe to slight limitations, depending on activity and topography.	Slight to moderate limitations. Reservoir may leak where rocks are fractured.	Severe limitations. Reservoir may leak where rocks are fractured.	Severe limitations. Rock excavation. Steep slopes.


* See discussions of swelling shales and soils



Alluvium deposited by the Rolling Fork provides fertile soils for row crops. Photo by Dan Carey, Kentucky Geological Survey.

Limestone and Dolomite—Unit 3

Limestone and dolomite of unit 3 in northern Marion County provide soils for a strong agricultural economy. Photo by Dan Carey, Kentucky Geological Survey.



An uplifting experience that will not be appreciated! Left: All is well in this newly built home until water from percolation, drains, lawn sprinklers, leaking sewers, or water mains soaks swelling soil beneath the foundation. Right: With time, expanding soils exert several tons per square foot of pressure on the foundation and shallow pilings. Without remedial measures, the house will actually become deformed, and shatter masonry and windows. Remedies vary from mere maintenance that keeps drainage away from the house to expensive reconstruction of foundations. Prior site planning that takes geology into account is always preferable to dealing with problems after a structure is built. From AIPG (1993).

Rural Residential Development




Rural residential development on unit 5 off Ky. 208. Nearby alluvial soil of Indian Lick Creek grows a healthy corn crop. Photo by Dan Carey, Kentucky Geological Survey.

Limestone, Siltstone, Shale—Units 5, 6, and 7



Limestone and siltstone layers (units 6 and 7) overlying the shale layer (unit 5) at this roadcut on U.S. 68/Ky. 55 near the Taylor County line provide a good illustration of these Mississippian (350 million years old) rocks. Photo by Dan Carey, Kentucky Geological Survey.

Siltstone—Unit 6




Laminated layers of siltstone in the Halls Gap Member of the Borden Formation (unit 6) are exposed at this roadcut on Ky. 208 south of Phillipsburg. Photo by Dan Carey, Kentucky Geological Survey.

Swelling and Shrinking Shales

A problem of some concern in Marion County is the swelling of some of the clay minerals in shale units 5 and 6. The process is exacerbated when the shale contains the mineral pyrite (fool's gold). Pyrite is a common mineral and can be found distributed throughout the black shale, although it is not always present and may be discontinuous both laterally and horizontally. In the presence of moisture and oxygen, pyrite oxidizes and produces sulfuric acid. The acid reacts with calcium carbonates found in water, the rock itself, crushed limestone, and concrete. This chemical reaction produces sulfate and can form the mineral gypsum, whose crystallization can cause layers of shale to expand and burst, disintegrate to swell, and concrete to crack and crumble. It can heave the foundation, the slab, and interior partitions resting on it, and damage upper floors and interior partitions. This phenomenon has been responsible for extensive damage to schools, homes, and businesses in Kentucky. During times of drought, these same shales may shrink, causing foundations to drop.

Anyone planning construction on these shales should seek professional advice from a geologist or engineer familiar with the problem.



Swelling Shale and Foundation Damage



Some shales, and the soils derived from them, swell when exposed to water or air. These swelling shales and soils can have severe impacts on building foundations and other structures (e.g., bridges, dams, roads). Photo by John Kiefer, Kentucky Geological Survey.

References Cited

American Institute of Professional Geologists, 1993. The geologist's guide to geologic hazards: 134 p.
Carey, D.I., and Stickeny, J.F., 2004. Groundwater resources of Marion County, Kentucky. Kentucky Geological Survey, ser. 12, County Report 75. www.uky.edu/KGS/water/brary/gw/marion.htm [accessed 6/20/06].
Crawford, M.M., 2004a. Spatial database of the Gravel Switch quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1506. Adapted from Moore, S.L., 1978. Geologic map of the Gravel Switch quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1506, scale 1:24,000.
Crawford, M.M., 2004b. Spatial database of the Mackville quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1378. Adapted from Peterson, W.L., 1972. Geologic map of the Mackville quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1378, scale 1:24,000.
Crawford, M.M., 2004c. Spatial database of the Raywick quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1048. Adapted from Kiefer, R.C., 1973. Geology of the Raywick quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1048, scale 1:24,000.
Federal Emergency Management Agency, 2004. www.fema.gov [accessed 4/20/06].
Johnson, T.L., 2004. Spatial database of the Howardsdown quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1161. Adapted from Moore, S.L., 1978. Geologic map of the Howardsdown quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-505, scale 1:24,000.
Kelley, J.A., and Craddock, W.H., 1991. Soil survey of Marion County, Kentucky. U.S. Department of Agriculture, Soil Conservation Service, 215 p.
Murphy, M.L., 2004a. Spatial database of the Bradfordville Northeast quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1396. Adapted from Moore, S.L., 1977. Geologic map of the Bradfordville Northeast quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1396, scale 1:24,000.
Murphy, M.L., 2004b. Spatial database of the Spurlington quadrangle, Marion and Taylor Counties, Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1161. Adapted from Moore, S.L., 1974. Geologic map of the Spurlington quadrangle, Marion and Taylor Counties, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1161, scale 1:24,000.
Nelson, H.L., Jr., 2004a. Spatial database of the Lebanon East quadrangle, Marion County, Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1508. Adapted from Moore, S.L., 1978. Geologic map of the Lebanon East quadrangle, Marion County, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1508, scale 1:24,000.
Nelson, H.L., Jr., 2004b. Spatial database of the Lebanon West quadrangle, Marion County, Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1509. Adapted from Moore, S.L., 1978. Geologic map of the Lebanon West quadrangle, Marion County, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1509, scale 1:24,000.
Nelson, H.L., Jr., 2004c. Spatial database of the Loretto quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1034. Adapted from Peterson, W.L., 1972. Geologic map of the Loretto quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1034, scale 1:24,000.
Nelson, H.L., Jr., 2004d. Spatial database of the Saint Catherine quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1252. Adapted from Peterson, W.L., 1975. Geologic map of the Saint Catherine quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1252, scale 1:24,000.
Nelson, H.L., Jr., 2004e. Spatial database of the Springfield quadrangle, Washington and Marion Counties, Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1380. Adapted from Peterson, W.L., 1977. Geologic map of the Springfield quadrangle, Washington and Marion Counties, Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1380, scale 1:24,000.
Paylor, R.L., Flores, L., Caudill, H., and Currens, J.C., 2004. A GIS coverage of karst sinkholes in Kentucky. Kentucky Geological Survey, ser. 12, Digital Publication 5, 1 CD-ROM.
Peterson, C., 2004a. Spatial database of the Bradfordville quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1396. Adapted from Moore, S.L., 1977. Geologic map of the Bradfordville quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1396, scale 1:24,000.
Peterson, C., 2004b. Spatial database of the Saloma quadrangle, central Kentucky. Kentucky Geological Survey, ser. 12, Digitally Vectorized Geologic Quadrangle Data DVQG-1391. Adapted from Moore, S.L., 1976. Geologic map of the Saloma quadrangle, central Kentucky. U.S. Geological Survey Geologic Quadrangle Map GQ-1391, scale 1:24,000.
U.S. Environmental Protection Agency, 2005. A citizen's guide to radon: The guide to protecting yourself and your family from radon. www.epa.gov/radon [accessed 8/31/06].
U.S. Fish and Wildlife Service, 2003. National Wetlands Inventory. www.nwi.fws.gov [accessed 4/25/06].



LAND-USE PLANNING TABLE DEFINITIONS

FOUNDATION AND EXCAVATION
The terms "earth" and "rock" excavation are used in the engineering sense; earth can be excavated by hand tools, whereas rock requires heavy equipment or blasting to remove.

LIMITATIONS


Slight—A slight limitation is one that commonly requires some corrective measure but can be overcome without a great deal of difficulty or expense.
Moderate—A moderate limitation is one that can normally be overcome but the difficulty and expense are great enough that completing the project is commonly a question of feasibility.
Severe—A severe limitation is one that is difficult to overcome and commonly is not feasible because of the expense involved.

LAND USES

Septic tank disposal system—A septic tank disposal system consists of a septic tank and a filter field. The filter field is a subsurface line system laid in such a way that effluent from the septic tank is distributed with reasonable uniformity into the soil.
Residences—Ratings are made for residences with basements because the degree of limitation is dependent upon ease and required depth of excavation. For example, excavation in limestone has greater limitation than excavation in shale for a house with a basement.
Highways and streets—Refers to paved roads in which cuts and fills are made in hilly topography, and considerable work is done preparing subgrades and bases before the surface is applied.

Access roads—These are low-cost roads, driveways, etc., usually surfaced with crushed stone or a thin layer of blacktop. A minimum of cuts and fills are made; little work is done preparing a subgrade and generally only a thin base is used. The degree of limitation is based on year-around use and would be less severe if not used during the winter and early spring. Some types of recreation areas would not be used during these times.
Light industry if not used—Ratings are based on developments having structures or equivalent load limit requirements of three stories or less, and large paved areas for parking lots. Structures with greater load limit requirements would normally need footings in solid rock, and the rock would need to be core drilled to determine the presence of caverns, cracks, etc.
Intensive recreation—Athletic fields, stadiums, etc.
Extensive recreation—Camp sites, picnic areas, parks, etc.
Reservoir areas—The floor of the area where the water is impounded. Ratings are based on the permeability of the rock.
Reservoir embankments—The rocks are rated on limitations for embankment material.

Underground utilities—Included in this group are sanitary sewers, storm sewers, water mains, and other pipes that require fairly deep trenches.




Gravel bars in the Rolling Fork River west of New Market. The Rolling Fork provides water for agriculture and communities. Photo by Dan Carey, Kentucky Geological Survey.

Additional Planning Resources

Listed below are Web sites for several agencies and organizations that may be of assistance with land-use planning issues in Marion County:
www.lebanonky.org—Lebanon/Marion County
www.lebanon-ky.com—Lebanon/Marion County Chamber of Commerce
www.uky.edu/extension/ukc—UK Cooperative Extension Service
www.laddc.org—Linn Trail Area Development District
www.thinkkentucky.com/visit/county/cv4042—Kentucky Economic Development Information System
www.uky.edu/KentuckyAtlas21155.html—Kentucky Atlas and Gazetteer
[www.quickfacts.census.gov/qd/states/21/21155.html](http://quickfacts.census.gov/qd/states/21/21155.html)—U.S. Census data
www.bae.uky.edu/extension/ResidentialRadonQandA.htm—Radon in the home
www.uky.edu/extension/landuse/marioncounty.htm—Planning information from the Kentucky Geological Survey


Copyright 2006 by the University of Kentucky, Kentucky Geological Survey.
For information on obtaining copies of this map and other Kentucky Geological Survey maps and publications call our Public Information Center at 859.257.3896 or 877.778.7827 (toll free).
View the KGS World Wide Web site at: www.uky.edu/kgs

Mineral Resources




Nally & Hayden LLC extract over 500,000 tons of limestone per year from unit 3 in this quarry and provide crushed stone and agricultural limestone to the county. Photo by Dan Carey, Kentucky Geological Survey.

7.5-Minute Quadrangle Map Index



Geology of Kentucky



Learn more about Kentucky geology at www.uky.edu/KGS/geology/